

- 1 METER SETTER INLET: COPPERTUBE PACK JOINT/OUTLET COPPERTUBE PACK JOINT SEE CURRENT APPROVED PRODUCT MANUFACTURERS SHEET FOR APPROVED TYPES (APPENDIX A)
- 2 METER TO BE INSTALLED BY THE CITY
- (3) METER BOX- SEE CURRENT APPROVED PRODUCT MANUFACTURERS SHEET FOR APPROVED TYPES. (APPENDIX A)
- (4) 24" OF COPPER W/BE USED FOR TAIL PIPE AND FIP x CTPJ W/BE PROVIDED FOR CONNECTION
- (5) ALL ITEMS AS SPECIFIED OR APPROVED EQUAL(DOMESTIC MANUFACTURED ONLY)
- (6) METER BOXES SHALL NOT BE LOCATED IN DRIVEWAYS OR DESIGNATED PARKING SPACES.
- 7 SEE STANDARD DETAIL W-12 FOR METER BOX LOCATION. IN AREAS WHERE SIDEWALKS ARE NOT REQUIRED THE BACK OF THE METER BOX SHALL BE LOCATED AT THE PROPERTY LINE.

CITY OF SALISBURY, N.C. STANDARD DETAIL	DATE: DCTOBER 17, 2006 AMENDED: MAY 19, 2009
WATER SYSTEMS	NOT TO SCALE
3/4" & 1 " METER DETAIL	STANDARD W-9